

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,
No.BBMP/EE/DD/Ten/03/2014-15, Date:31.10.2014.

ITEM NO: 12

SCHEDULE-B

NAME OF WORK: Providing improvements to roads & Drains at Medarahalli Pillappa layout & R.R layout, in ward no.12, in Shettyhalli Sub-Division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor K M RAVI	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	333.2	72.6	Rupees Seventy Two and Sixty Paise Only
2	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	147.38	100.84	Rupees One Hundred and Eighty Four Paise Only
3	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	435.6	629.36	Rupees Six Hundred Twenty Nine and Thirty Six Paise Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.86cum and fine aggregate @ 0.58cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	146.4	4700.04	Rupees Four Thousand Seven Hundred and Four Paise Only
5	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregate @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	12.96	5250.64	Rupees Five Thousand Two Hundred Fifty and Sixty Four Paise Only

Signature of the Contractor

Executive Engineer

6	Providing and laying cement concrete using 20mm and down size 1 unite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15-mm thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1:5:3) for raft foundation, column footing, main and secondary beams. Complete as per specification and direction of Engineer-in-charge of the work.	Cum	100.17	5750.12	Rupees Five Thousand Seven Hundred Fifty and Twelve Paise Only
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specification and direction of Engineer-in-charge of the work.	Q	6.13	7800.8	Rupees Seven Thousand Eight Hundred and Eighty Paise Only
8	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	43.2	287.68	Rupees Two Hundred Eighty Seven and Sixty Eight Paise Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	480.58	71.71	Rupees Seventy One and Seventy One Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,